

Halvering & Stroud Kitchens

Design, cabinetry and installation 41 Tannery Wharf Road, Halden Cross. Office 555-0142. Contractor license HIC-0448217.

Kitchen Renovation Quote

- Quote number: HS-2291
- Revision: A
- Issued: Thursday 18 June 2026
- Prepared by: Dunmore Kessane, Estimator
- Prepared for: Ottilie Varnhagen and Jorrit Aldemere
- Property: 14 Fennimore Row, Halden Cross

Thank you for having us out on 9 June. This quote prices the layout we sketched together at the kitchen table: the range on the north wall, the sink under the window, and a long island where the peninsula is now.

Scope of work and prices

1. Demolition and site protection. Remove the existing cabinets, countertops, backsplash tile and peninsula; protect the floor; haul away debris. \$1,700.
2. Cabinetry. Semi-custom maple shaker cabinets, factory painted: 10 base cabinets, 8 wall cabinets and 1 tall pantry cabinet, with soft-close hinges, standard drawer slides, crown molding, toe kicks, delivery and installation. The price includes decorative hardware: up to 38 knobs and pulls from our standard brushed range, fitted. \$15,250.
3. Countertops. 2 cm quartz with a built-up edge, approximately 46 sq ft on the perimeter run, one undermount sink cutout, templating and installation. \$4,900.
4. Island. Freestanding island measuring 7 ft x 3 ft: three base cabinets, matching quartz top and one dedicated electrical outlet. \$5,600.
5. Backsplash. Ceramic subway tile, approximately 28 sq ft, straight lay, grouted and sealed. \$1,850.
6. Plumbing and electrical. Reconnect the sink, disposal and dishwasher in their existing locations; two new countertop outlets; four recessed LED lights. \$2,950.
7. Appliance allowance. \$5,000 toward a range, range hood and dishwasher bought through our supplier. The existing refrigerator is reused.
8. Permit and inspection fees. \$600.

Contract total: \$37,850. Sales tax on materials is included in the prices above.

Not included

- Flooring. The existing floor stays, and the area under the old peninsula is left for the owners' flooring contractor.
- Painting of walls and ceiling after installation.
- A new sink or faucet. The owners supply both.

Payment schedule

- Deposit on acceptance: a flat \$4,500.
- On delivery of the cabinets to site: half of the remaining balance, \$16,675.
- On completion: the remaining \$16,675.

Payment is by check or bank transfer.

Schedule

- Start on site: Monday 14 September 2026.
- Time on site: an estimated 5 working weeks.
- Target completion: Friday 16 October 2026.
- Crew hours: 8:00 am to 4:30 pm, Monday to Friday.

To hold the September start we need this quote accepted and the deposit received by Friday 17 July 2026. This quote is valid for 30 days from the date of issue.

Unforeseen conditions

Hidden conditions found once walls or floors are opened, such as water damage or wiring that does not meet code, are billed on a time-and-materials basis at \$85 per hour plus materials. We will tell you before we start any such work.

Warranty

Our workmanship is warranted for one year from completion. The cabinets carry the manufacturer's limited lifetime warranty.

Acceptance

Signed for Halvering & Stroud Kitchens: Dunmore Kessane, 18 June 2026

Owner acceptance: _____ Date: _____

Owner acceptance: _____ Date: _____